

Excessive Project Cost – Where It Comes From: A Quantum Perspective

Ilya Fishman (Ibico, Inc.)
David R. Graham (AFCAA/SMC/OL)

2009 ISPA / SCEA Professional Development and Training Workshop

UnderEstimating Project Costs: *Error or Lie?*




FIGURE 1. Inaccuracy of cost estimates in 258 transportation infrastructure projects (fixed prices).

“... a pattern of highly misleading forecasts of costs and patronage could not be explained by technical issues and were best explained by lying”

Flyvbjerg, Holm, Buhl, APA Journal, 2002, No. 3

Cost Underestimate in NASA & DoD Projects

Study	Cost/Budget Growth		% overruns
	Average	Median	
NASA in the 90s	36%	26%	78%
NASA in the 70s	43%	26%	75%
NASA in the 80s			
Gruhl study	61%	50%	95%
GAO study	83%	60%	89%
DoD	45%	27%	76%

Source: Schaffer, 2004

Project Statistics and Central Limit Theorem





FIGURE 1. Inaccuracy of cost estimates in 258 transportation infrastructure projects (fixed prices).

CLT:

“Sum of a sufficiently large number of independent random variables, each with finite mean and variance, will be approximately normally distributed”

How to Foresee the Contingency?



Problem:

Planners suggest what they consider Mean task costs or durations

Solution:

Separate planning from risk estimate, seek possible delays / overbudgets from risk experts



Task and Milestone Distribution Functions




FIGURE 1. Inaccuracy of cost estimates in 258 transportation infrastructure projects (fixed prices).



What Theory Should Do

- Risk analysis should start with *symmetric* task distributions (directly or indirectly implied by planners),


and

- *Predict* milestone distributions skewed to longer times and higher budgets

Quantum Model and Milestone Image




Schedule Risk (No Input)




- Task distributions are normal with CoV = 13%, milestone probability density is asymmetric and predicts ~ 4 years contingency

“Internal” Input: Reduced Task CoV





- Task distributions are normal with CoV = 1%, milestone probability density is asymmetric and predicts ~ 100 days contingency

“External” Input: Very Low Risk




- Task distributions are normal with $CoV = 13\%$,
- Risk is very small,
- Milestone probability is almost symmetric with ~ 150 days contingency.

How It Works -1 Project Sample




300 Monte Carlo Simulated Project Samples




Mean of milestone image is shifted to *later date*

$$P = \sum_{\tau} [\psi_1(t, \tau) + \psi_2(t, \tau) + \psi_3(t, \tau) + \psi_4(t, \tau)]^2$$




3000 Project Samples, 1% Task CoV


CoV = 11%





CoV = 1%



TaskID	CoV(%)	TaskName	Duration
1	11	Requirements definition Spacecraft	100
5	11	FS preliminary design	300
6	1	US Preliminary design	450
7	1	FS Final Design	600
8	11	US Final design	100
9	11	FS Fabrication	300
10	1	US Fabrication	450
11	1	Test US Engine	600
12	11	US Test	100
13	11	Integration	250




Conformity to Classical Monte Carlo Analysis



Milestone quantum image is calibrated against classical Monte Carlo simulations: task and milestone CoVs are equal

Conformity to Classical Monte Carlo Analysis

Risk Category		Risk Likelihood and Consequence				
Cost risks						
<input checked="" type="checkbox"/>	Funding stability	Green	Orange	Red	Red	Red
<input checked="" type="checkbox"/>	Supplier financial viability	Green	Yellow	Orange	Orange	Red
<input type="checkbox"/>	Other					
Performance Risks						
<input checked="" type="checkbox"/>	Immature Technology - TRL was too low or assessed too high	Green	Green	Yellow	Orange	Red
<input checked="" type="checkbox"/>	Requirements volatility	Green	Green	Green	Yellow	Orange
<input checked="" type="checkbox"/>	High percent new design required	Green	Green	Green	Green	Green
<input type="checkbox"/>	Extent to which existing hardware or software can be reused	Green	Green	Green	Green	Green
<input type="checkbox"/>	Activities take longer because they are more complicated than estimated	Green	Green	Green	Green	Green



All risks corresponding to $CoV_{task} = CoV_{milestone}$ are considered “average”

Maximum risks correspond to task $CoVs = 0.25$ (system parameter)

Summary

- Projects are delayed and costs are overrun by currently unknown *details of project tasks and their mutual correlations*
- These details and correlations are modeled by *interference* of quantum mechanical wave functions
- Wave function interference pattern is milestone probability density
- Monte Carlo simulated milestone probability distribution is *naturally asymmetric*
- Fully symmetric task *uncertainties* are converted into milestone *risk*.